



**Bexar County
Infrastructure Services
Flood Control CIP Program**

Project: LC 9

Hausman Drainage Project Phase I

Location / Limits: Hausman Road between Huntsman Rd and Babcock Rd



SCOPE :

This project will consist of replacing 3 low water crossings with bridges and downstream channel improvements to provide unflooded access during the 1% chance rainfall event along Hausman Road between Babcock and Huntsman. There will be buyouts downstream of the three crossings in the existing Valley View Subdivision for those residences that will not have unflooded access, as well as mitigation and channel improvements purposes.



Precinct:	3	OCL/ICL:	I.C.L.	C.D. 8
Watershed:	Leon Creek			
Creek Name:	Huesta Creek			
Project Type:	Low Water Crossing			

Consultant:	CP&Y, Inc.
Consultant Awarded:	8 /19/2008
Contractor:	TBD
Contractor Awarded:	
Construction Start:	Jul 2011
Construction End:	Jan 2013

Estimated Construction Cost:	\$8,700,000
-------------------------------------	-------------

PROJECT STATUS	Detailed Design
-----------------------	-----------------

